

Domenica Valley Villas

Specifications and Technical Details

1.0.0. Foundation and Framework

Reinforced concrete, beams and slabs, designed per Eurocode earthquake design standards.

2.0.0 Walls

2.1.0. External Walls:

Thermal insulation system in accordance to class "A" guidelines, consist of:

1. 20-25cm thick brick work
2. 5-8cm polystyrene
3. Decorative acrylic paint or Graffiato paint or sandex paint in external verandas according to architects request.

2.2.0. Internal Walls:

10cm thick.

Cement – Sand 2 or 3 coats plastering.

Decorative Emulsion paint (where applicable)

3.0.0. Floor and walls tiles

Lightweight concrete above the reinforced concrete slabs for sound and thermal insulation.

3.1.0. Internal area flooring

Imported Ceramic tiles at Euro 14.00/ sq. m or high quality laminate parquet flooring (wide range of designs available) from the Company's range.

3.2.0. Verandas

Imported Ceramic floor tiles at Euro 14.00/ sq. m (wide range of designs available) from the Company's range.

3.3.0. Staircase

Marble Ajax, Perlato 20mm or equivalent

3.4.0. Bath, shower and toilet rooms

Imported Ceramic floor tiles at Euro 14.00/ sq. m (wide range of designs available) from the Company's range.

Imported Glazed wall tiles (up to door height) at Euro 14.00/ sq. m (wide range of designs available) from the Company's range.

3.5.0. Kitchen wall tiles

Imported Glazed tiles at Euro 14.00/ sq. m (wide range of designs available) from the Company's range.

Domenica Valley Villas

Specifications and Technical Details

4.0.0. Kitchen cabinets

Custom made kitchen cupboards made of high quality MELAPAN finish.
Technogranite countertop 40mm with provision for cooker, re-circulation hood, washing machine and refrigerator (Appliances not included) at Euro 95.00/m from the Company's range

5.0.0. Bedroom cupboards

Custom made floor to ceiling wardrobes, externally made of high-quality MELAPAN finish out of Company's range

6.0.0. Living Area Wall Unit

Custom made wall mounted unit made of high quality MELAPAN finish out of Company's range, according to Architectural drawings.

7.0.0. Doors

7.1.0. Entrance door

Sound and weather insulated aluminium door.

7.2.0. Internal doors

Flush MELAPAN finish

8.0.0. Aluminium patio doors and windows

Upgraded thermal aluminium series.

Double-glazed thermal insulation glass.

Aluminium sliding / opening doors and windows MU 3000 THERMAL & MU 2075 series, improving thermal and sound insulation.

9.0.0. Sanitary fittings

Branded high quality European sanitary fittings, taps, mixer taps, sinks, accessories, glass screens, mirrors, installation accessories etc. like Grohe, Hansgrohe and more, of total cost Euro 1500.00

10.0.0. Protective rails on upstairs verandas and roof garden (if any)

Frameless Glass railings, according to Architectural request.

11.0.0. Decorative elements on the facade

11.1.0. Stone work or HPL panels or vertical slats or any other exterior elements, according to Architectural drawings or Authority permission.

Domenica Valley Villas

Specifications and Technical Details

12.0.0. Paint

- 12.1.0. Walls and ceiling
Emulsion paint
- 12.2.0. Interior timberwork
Semi-matt
- 12.3.0. Exterior timberwork (if any)
Durable wood stain

13.0.0. Electrical installations

High quality electrical installation, according to European standards and electricity authority approval.
Concealed circuits and all other installations, in compliance with the Electricity of Cyprus (EAC) regulations, with comprise of circuits for light fixtures and power points for kitchen appliances, TV, telephone, provisions for a/c units, provision for satellite TV (pipe & box of satellite TV) solar heater and other power points.

14.0.0. Mechanical

- 14.1.0. Hot and cold water supply in all designed areas.
- 14.2.0. Central heating provision in all rooms
- 14.3.0. A/C provision in all rooms
- 14.4.0. Bathroom hot water supply
Electrical heater and solar panels

15.0.0. Parking area with fine concrete finish

16.0.0. Boundary walls

Plastered and rendered according to the architectural request.

17.0.0. Special terms

- 17.1.0. Stone work according to Architectural drawings.
- 17.2.0. HPL panels on the facade, according to Architectural drawings.

Notes:

- a) **In case the client wishes to use materials out of the Company's range, a fee of 15% of the price currently stated above in the specifications will be charged.**
- b) **In case the client wishes to appoint any external provider / supplier for specific works, this can be done only with the accordance of the company and an additional fee of 5% will be added to cover overheads and required assistance.**

MEDITERRANEAN PACKAGE